

Italy Demo Case

Ex-situ BioMethanation

Samuele Vito, CAP Holding

Barcelona, 29th November 2024




Co-funded by
the European Union



innovations in the
BIOMETHA^{ne}
uni**VERSE**

Brief description of the site



Experimental site for the Italian case is in the Wastewater treatment plant of Bresso-Niguarda, which is located in the city of Milan and managed by CAP.

It is a 320.000 P.E. urban wastewater treatment plant, with two parallel anaerobic digestion lines **for sludge treatment and valorization to biogas.**

In 2018 in the Bresso-Niguarda WWTP was installed the first biogas upgrading plant to obtain biomethane from sewage sludge-produced biogas.

Currently, the plant produces about **600.000 m³** per year that are injected to the national distribution grid.



Description of innovative technology

CAP, in collaboration with partners Politecnico di Milano, SIAD and CIC, will implement an **integrated demo plant**, to achieve a **more sustainable biomethane production**.


The project aims to highlight the positive outcomes of the **integrated model**, utilizing synergies to maximize **environmental benefits** and secure **economic sustainability**.

Two main units:

- The feedstock pre-treatment via ozonisation allows to increase the biogas yield from sewage sludge
- The upgrading unit (EBM) converts produced biogas into biomethane via an ex-situ hydrogen promoted biological upgrading process.

Two auxiliary units:

- The raceway pond where microalgae cultivation treats nutrients and pollutants from a wastewater stream providing new biomass
- The biomass is co-digested with sewage sludge, increasing bio-gas production.



CAP



POLITECNICO
MILANO 1863

SIAD



Co-funded by
the European Union

Challenges and criticalities of technology

Pre-treatment via ozonolysis

Avoid ineffective transfer yields and malfunctions related to clogging problems

Ex-situ biological upgrading


Increase the efficiency of H_2 mass-transfer and the process yield under variable feed flow

Co-digestion pilot

Fast and reliable analytical tools for supporting of digester modelling are currently one of the main bottlenecks for process modelling integration at real scale facilities.

Overall

Develop a comprehensive framework to evaluate the synergies between pilots optimizing the aggregated impacts



What done so far

Ozonolysis

- Initial laboratory tests: optimal ozone dosage, protein solubilization, TSS reduction, mineralization,...
- Then, ozonolysis contact reactor was designed
- Safety measures and electrical designs were implemented
- Construction phase: 12 m³ oxygen tank, the ozone generator and the contact reactor.
- Integration into the existing WWTP with the support of plant technicians.
- Safety inspections and successful trials using regular water
 - ▶ **Full-scale treatment of wastewater sludge was initiated.**

EBM

- Membrane selection and inoculation of 1 membrane unit, Gas Transfer Membrane (GTM) testing in feed/dead-end flow
- Laboratory-scale tests: biofilm hydrogen conversion rates and nutrient uptake.
 - ▶ **The EBM pilot plant was installed in LIA lab in Polimi, tested in blank and put into operation once completed the installation of all security devices.**
- Modelling of start up conditions for suspended biomass bubble column reactor completed (column on the right).
- Modelling of membrane biofilm reactor (ongoing)



What done so far

Co-digestion

- Lab test: Anaerobic degradability of sludge, microalgae, and their mixtures was evaluated.
- Batch BMP tests were conducted on various mixed matrices to assess their biogas production potential.
- Semi-continuous co-digestion at a laboratory scale.
- **Existing co-digestion pilot plant was revamped.** Finally, the equipment was transported and under installation at the Bresso WWTP (operation will start in spring 2024 when algae will be available)

Microalgae Cultivation

- During 2023 and 2024 (352 days of operation), **verification of productivities and nutrient removal** → according to the expected values

Site Preparation

- Completed basement structural design and construction
- Revamped conventional membrane upgrading unit
- Configured piping systems
- Assessment to ensure compliance with safety certifications (CPI, ATEX)



Future activities

Full-scale ozonolysis:

- a) Achieve full-scale ozonolysis of sludge in a continuous process.
- b) On-line data monitoring and analytical campaigns.

EBM:

- a) Completion of pilot scale testing and optimization of EBM reactor in Polimi laboratory
- b) 1-D Biofilm and Gas-liquid transfer model finalization.

Microalgae cultivation:

Pilot-scale production of microalgae biomass for co-digestion pilot tasting (from spring 2025)

Co-digestion:

- a) Lab-scale co-digestion tests with ozonated algae (on going)
- b) Pilot-scale start up expected in spring when algae biomass will be available



Thank you!

Follow Biomethaverse:

www.biomethaverse.eu 

[@European_Biogas](https://twitter.com/European_Biogas) 

[@European Biogas Association](https://www.linkedin.com/company/european-biogas-association/) 

Email: tomaso.amati@gruppocap.it
samuele.vito@gruppocap.it

